

## SCHEDULE OF WORK FOR ILLUMINATION OF ANCHOR AT COPT AVENUE WALKWAY

Sl.	Description of Items	Unit	Qty	Rate (Rs)	Amount (Rs)
1	Design, supply, installation, testing and commissioning of external sign board with content "COPT AVENUE" ( Letter 1 feet height and 3 inch thickness) in English as per the tech specification in Annexure -II	Set	1 ( set of 10 letters)		
2	Design, supply, installation, testing and commissioning of external sign board with content "WALKWAY" (Letter 15 inches height and 3 inch thickness) in English as per the tech specification in Annexure -II	Set	1 (1 set of 7 letters)		
3	Design supply installation and testing and commissioning of acrylic wall mounted Signboard of size 150cm x 40cm milky white acylic sheet as base of 3mm thickness. Letters and logo with laser cut acrylic letters of thickness 3mm.	Set	1		
4	Supply,Installation, Testing and Commissioning of 15W LED Warm white surface mounted beam spot lighting	Nos	4		
5	Shade lighting with water proof LED strip 12 V , fixing with LED casing warm color LED	m	20		
6	Supply and providing necessary DBs/Junction boxes and cabling	LS	1		
	Total Amount without GST				
	GST				
	Total Amount with GST				