

COCHIN PORT TRUSTwww.tenderwizard.com/CPT

Tender No: T6/T-1952/2021-C Date: 03.11.2021-(PRICE BID)

Name of Work: "PROVIDING CONCRETE PAVER TILES AT APPROACH OF RO-RO JETTY AT BOLGHATTY"**SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT**

Please Enter the Contractor Name							
Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Providing, laying, spreading and compacting graded stone aggregate(size range 53 mm to 0.075 mm) to wet mix macadam (WMM) specification including premixing the material with water at OMC in mechanical mix plant for all leads & lifts, laying in uniform layers with mechanical paverfinisher in subbase / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, including cost of all labour, materials, equipments, tools etc. complete as per detailed specifications and directions of Engineer-in-Charge.	45.00	One cubic metre	3589.22	Rupees Three Thousand Five Hundred Eighty Nine and Twenty Two Paise Only	161514.90	Rupees One Lakh Sixty One Thousand Five Hundred Fourteen and Ninety Paise Only

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
2	Providing and laying factory made 100mm thick Cement Concrete paver blocks of M40 grade, thickness & size/ shape, made by table vibratory method , to attain superior smooth finish using PU or equivalent moulds, laid in required colour & pattern over 50mm thick compacted bed of 6mm coarse aggregate, compacting and proper embedding / laying of inter locking paver blocks into the 6mm coarse aggregate bedding layer through vibratory compaction by using plate vibrator, filling the joints with crusher sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in drive ways or traffic parking including cost of all labour, materials, equipments etc. complete as per manufacturer's specifications/ detailed specifications & direction of Engineer -in-Charge.	480.00	One square metre	1030.00	Rupees One Thousand Thirty Only	494400.00	Rupees Four Lakh Ninety Four Thousand Four Hundred Only

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
	Total					655914.90	Rupees Six Lakh Fifty Five Thousand Nine Hundred Fourteen and Ninety Paise Only
BIDDER'S QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail 5.Wrongful entry of quotes shall entail disqualifications besides other actions as the Employee deem fit.				655914.90			
" This is a Electronic Submission No Need of Signature"							