

COCHIN PORT AUTHORITY



**Chief Engineer's Office
Cochin Port Authority
W/Island , Cochin – 682009, KERALA
Tele: 91-0484-2666414/0484-258-2400
website: www.cochinport.gov.in**

No. T6/BI/Fender/2023-C

Date : 20/01/2023

NOTICE INVITING BUDGETARY INQUIRY

Budgetary Inquiries are invited by the Cochin Port Authority (CoPA) from reputed experienced firms for Supplying and installing Cell Type Rubber Fenders 1700H at COT.

BACK GROUND.

Cochin Port Authority (CoPA) is contemplating for the replacement of damaged 1700 H Cell Type Rubber Fenders at COT. Features and Scope of the proposed work are as below.

- i. Dismantling and removing 3 Nos. existing / damaged Cell type Rubber Fenders.
- ii. Supplying 4 Nos. 1700H Cell Type Rubber fender and stacking the same at Ernakulam Wharf or location pointed out by the Engineer-in-Charge.
- iii. Installing 2 Nos. new & 1 No. existing 1700H Cell type rubber fender at COT. Access to COT is through water only which is about 500m away from Ernakulam Wharf. Floating crane for the mobilisation of Fenders will be allotted at free of cost.

The proposed project site is located at Cochin Oil Terminal (COT) at Ernakulam Chanel.

It is proposed to invite tenders for the proposed work shortly. In this regard, you are requested to furnish your budgetary rates for the supply and installation of 1700H Cell Type Rubber fender at COT in the *Annexure-I* attached. GST may be shown separately.

The bidders are requested to submit the **Budgetary rates** as per *Annexure-I* attached and may be sent in sealed cover superscribing "**Budgetary Rates for Supplying and fixing 1700H Cell Type Rubber Fender at COT**", to the Suptd. Engineer(CM),

Cochin Port Authority, Willingdon Island, Cochin-09 (e-mail: sathyam@cochinport.gov.in) so as to reach us on or before **30-01-2023 at 17:00 hrs.**

The bidders may note that the rates are invited only for **budgetary** purpose. Cochin Port is not bound to award the work to any bidders based on the **budgetary** rates submitted. Cochin Port Authority will not be liable for any financial obligation to the bidders in connection with the preparation of their budgetary rates.

Sd/-
Suptdg. Engineer(CM)
Cochin Port Authority

Name of work : Supplying and fixing 1700H Cell Type Rubber Fender at COT.

Item No	Description of item	Unit	Rate
1	Dismantling the existing/ damaged cell type Rubber Fender 1700H along with all accessories and fixtures such as frontal frame, bolts, nuts, etc. and fixing the supplied/ existing fender to the same location to the correct line and level including cost of labour, materials, tools etc. complete as per detailed specifications and directions of the Engineer-in-charge. Floating cranes for mobilisation of new and dismantled fenders will be allotted at free of cost.	1 No.	
2	Supplying cell type Rubber Fender 1700 H at Ernakulam Wharf or the specified location at Willingdon Island along with all accessories and fixtures such as frontal frame, frontal pad, anchor bolt, u-hooks, chains etc. including all cost of loading/ unloading with necessary labour/ machinery etc. complete as per detailed specifications and directions of the Engineer-in-charge..	I No.	

Signature of Bidder