

GENERAL CONDITIONS

1. Work consists of "REPLACEMENT OF SHEARED BOLTS OF CRANE RAIL FIXING SYSTEM AT 'AMBA' JETTY AT COCHIN PORT" as per the Schedule of Quantities of work.
2. You shall inspect the site and clarifications, if any, required can be obtained before quoting for the work.
3. The work shall be completed within 3 weeks from the date of receipt of Work Order.
4. The Engineer-in-Charge of the work shall be Exe. Engineer (I), Civil Engineering Department, CoPA
5. Payments will be made online after deducting the taxes prevailing in force at the time of payment of bills.
6. The rate/percentage quoted shall be excluding Goods & Service Tax (GST).
7. The Contractor shall have valid GST Registration number. GST as applicable for the work will be paid extra by the Port. The GST applicable as per law can be billed, which will be paid to the Quotationer along with the bills, for which the Quotationer shall hold valid GST Registration number.
8. All materials, tools, plants, equipments etc required for completing the work shall be provided by the Contractor at his own cost. The materials required for the work shall be got approved by the Engineer-in-Charge before using in the work. All materials used for the work shall be of approved quality. All works shall be carried out as per relevant IS Standards.

9. All labour, skilled or unskilled, for the work shall be provided by the Contractor at his own cost and settling any disputes with the labour shall solely be the Contractor's responsibility.
10. All care and safety precautions/measures for avoiding any kind of damage/accidents in the work site shall be taken by the Contractor, while carrying out the work. The Contractor shall supply the necessary safety equipments to the workers employed by him and also ensure that they use it, while carrying out the work. The Contractor shall be solely liable and responsible for accidents if any, occurring during the period of Contract.
11. The work shall be completed without causing any damage to the existing structures. In case any damage is caused, the same has to be rectified at Contractor's risk and cost.
12. The Port will in no way be responsible for any loss/ damages caused in connection with the work.
13. In case the works are not completed within the specified completion period due to any fault of the Contractor, it will be considered as a breach of contract and the Contractor will not be considered for any other work in future.
14. The site of work is a protected area. Entry to 'Amba' jetty is regulated by entry pass issued by Gol. The bidder shall furnish list of person and equipments for whom pass has to be issued so as to enable the Engineer-in-Charge to arrange to obtain the entry passes from the appropriate Authority.
15. The work consists of "Replacing sheared Bolts of Crane Rail System with new galvanized M20 x 250mm Anchor Bolts of Grade 4.6 with M20 nut and washer (Hilti or equivalent) by carrying out metal/concrete coring

with a diameter not less than 25mm for a depth not less than 215mm and filling the hole with Polyester Resin Bolt Grout" as per As-Built Drawing attached, all complete as directed by the Engineer-in-Charge.

SIGNATURE OF QUOTATIONER