

COCHIN PORT AUTHORITY

NAME OF WORK: REPLACEMENT OF SHEARED BOLTS OF CRANE RAIL FIXING SYSTEM AT 'AMBA' JETTY AT COCHIN PORT

SCHEDULE OF QUANTITIES OF WORK

Sl No:	Description of work	Quantity	Unit	Rate (Rupees)	Amount (Rupees)
1.	Replacing sheared Bolts of Crane Rail System with new galvanized M20 x 250mm Anchor Bolts of Grade 4.6 with M20 nut and washer (Hilti or equivalent) by carrying out metal/concrete coring with a diameter not less than 25mm for a depth not less than 215mm and filling the hole with Polyester Resin Bolt Grout as per As-Built Drawing attached, all complete as directed by the Engineer-in-Charge	9.00	Nos.	7555.55	67999.95
	Total				67999.95
(Rupees Sixty Seven thousand Nine hundred Ninety Nine Paise Ninety Five only)					

Percentage quoted above / below the departmental rates shown in the above schedule:

In figures

In words

Signature of Quotationer

Note:- The quotationer shall quote either plus or minus, both in sign and in words, viz., (+) Plus / (-) minus.