## COCHIN PORT AUTHORITY

www.tenderwizard.com/CoPT



Tender No: T15/T-2000/2024-C Date: 28-02-2024 - PRICE BID

कोचिन पत्तन प्राधिकरण **Cochin Port Authority** 

## Name of Wok: "DREDGING FOR MAINTENANCE OF CHANNELS AND BASINS AT COCHIN PORT FOR THREE YEARS FROM 2024-25 TO 2026-27"

## SCHEDULE- II - SCHEDULE OF QUANTITIES (SoQ) TO BE DONE ON CONTRACT

Please Enter the Contractor Name					
				BIDDER'S QUOTING AREA	
Sl. No:	Sub- heads and items of work	Approximate Quantity	Unit	Amount (Rs.) In figures	Amount (Rs.) In words
1	Dredging for maintenance of Cochin Port Channels viz. Outer channel(CH:00 to CH:13150), Entrance channel from 0.00 chainage to the end of ICTT basin (Entrance Channel), LNG basin, ICTT basin and inner channels and basins (Ernakulam channel) & Mattancherry channel and berth frontage, etc.) Gol jetty basin adjacent to sector ECB- 5, MULT jetty basin adjacent to LNG Terminal, ICG jetty basin in Mattancherry channel and other areas within Cochin Port Limit on need basis to the required widths and depths by continuously deploying two Trailing Suction Hopper Dredger(s)[TSHD(s)] with a total hopper capacity not less than 11,000cu.m and minimum capacity of each dredger not less than 3,000 cu.m, as per Drawing No. 9777-01-2024 dtd.12/02/2024 and 9777-02-2024 dtd.12/02/2024 and disposing/dumping the dredged material evenly in the locations specified in the attached Drawing No. 9777-03-2024 dtd.12/02/2024 etc. complete as per detailed technical specifications, Special Conditions of Contract, General Conditions of Contract etc. and directions of the Engineer, for three years. Dredging in other areas / locations within Cochin Port limits as directed shall also to be done. The work includes cost of conducting all surveys, cost/hire charges of survey launch, cost of fuel, all plants, labour, material, etc complete. (excluding GST as applicable). For three years from 2024-25 to 2026-27	1.00	LS		
2	Recycling of dredged material from the channels and basins for reuse, at contractor's own risk and cost, with the approval of Employer and taking away the recycled materials by the contractor subject to complying with the statutory prevailing rules, etc. complete as per the directions of the Engineer. [Note: The Contractor shall indicate the quantity of dredged material proposed to be reused / recycled and to be taken away and lumpsum amount that can be offered to the Employer (excluding GST as applicable) towards the material that shall be reused / taken away. The amount so offered will be deducted from the amount quoted against item No.1 for evaluation purpose]		cum		
	NET AMOUNT [1-2] [Rupees in figures and in words] (excluding GST as applicable)				
	Notes:				

- (a) In case of discrepancy in words and figures, the quoted figure in words will prevail.

  (b) Wrongful entry of quotes shall entail disqualification as the Employer deem fit including forfeiture of EMD.

  (c) Please complete all the highlighted cells before submission

purpose, the Total Quoted Amount = The amount quoted against item No.1 of SoQ - The amount quoted against item No.2 of SoQ.

(d) For tender evaluation