

**ADDENDUM/ CORRIGENDUM NO.I  
COCHIN PORT AUTHORITY**

An ISO-9001:2015 & ISPS Compliant Port

Phone: 2666414

Telefax:91048 266414

E-mail : [ce@cochinport.gov.in](mailto:ce@cochinport.gov.in), [coptce@gmail.com](mailto:coptce@gmail.com)

Website: [www.cochinport.gov.in](http://www.cochinport.gov.in)

No. T6/T-2015/2024-C

**CHIEF ENGINEER'S OFFICE  
COCHIN-682009**

Dated: 21-08-2024

**TENDER FOR "PROVIDING DUCTILE IRON FRESH WATER SUPPLY PIPE  
LINE TO THE PLOT ALLOTTED TO CSL FOR ISRF AT MATTANCHERRY  
HALT"**

**(Tender No. T6/T-2015/2024-C)**

Item No.1 & 3 of Schedule-A- Schedule of quantities to be done on contract shall be amended as detailed below:-

**Existing Item No 1**

Sl. No :	Sub- heads and items of work	Approxi- mate Quanti ty	Unit	Departme ntal rates (Rs) in figures	Department al rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including consolidating each deposited layer by ramming, watering, etc. and	300.00	One Square Metre	494.6	Rupees Four Hundred Ninety Four and Ninety Six Paise Only	148488.00	Rupees One Lakh Forty Eight Thousand d Four Hundred Eighty Eight Only

	disposing of surplus excavated soil as directed, within a lead of 50 m : All kinds of soil Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia as per detailed specifications and directions of Engineer-in-Charge.						
--	--	--	--	--	--	--	--

**Amended Item No 1**

Sl. No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Excavating trenches of required width for pipes, cables, etc including excavation for sockets, and dressing of sides, ramming of bottoms, depth upto 1.5 m, including getting out the excavated soil, and then returning the soil as required, in layers not exceeding 20 cm in depth, including	300.00	Metre	494.6	Rupees Four Hundred Ninety Four and Ninety Six Paise Only	148488.00	Rupees One Lakh Forty Eight Thousand Four Hundred Eighty Eight Only

	consolidating each deposited layer by ramming, watering, etc. and disposing of surplus excavated soil as directed, within a lead of 50 m : All kinds of soil Pipes, cables etc. exceeding 80 mm dia. but not exceeding 300 mm dia as per detailed specifications and directions of Engineer-in-Charge.						
--	--	--	--	--	--	--	--

**Existing Item No 3**

Sl. No :	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Providing and laying Ductile Iron Pipes conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-9 pipes including cost of all labour, materials, tools,	300.00	One Square Metre	2192.27	Rupees Two Thousand One Hundred Ninety Two and	657681.00	Rupees Six Lakh Fifty Seven Thousand Six

equipments etc. complete the directions of the Engineer-in-charge.					Twenty Seven Paise Only		Hundred Eighty One Only
--	--	--	--	--	-------------------------	--	-------------------------

**Amended Item No 1**

Sl. No:	Sub- heads and items of work	Approx i-mate Quantity	Unit	Departme ntal rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Providing and laying Ductile Iron Pipes conforming to IS : 8329 : 150 mm dia Ductile Iron Class K-9 pipes including cost of all labour, materials, tools, equipments etc. complete the directions of the Engineer-in-charge.	300.00	Metre	2192.27	Rupees Two Thousand One Hundred Ninety Two and Twenty Seven Paise Only	657681.00	Rupees Six Lakh Fifty Seven Thousand Six Hundred Eighty One Only

All other terms & Conditions of tender remain unchanged.

**Sd/-**  
**SUPTDG. ENGINEER-I**