

COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Tender No: T6/T-2022/2024-C Date: 16.08.2024- (PRICE BID)

Name of Wok: "Providing 4 numbers 450mm dia. (25.00m length) Tubular Fender Piles & providing Ladder at MULT (Retender)"

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT							
Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
A	Part-A- 450mm Dia Tubular fender Pile						
1	Fabricating and supplying 450mm dia(OD) tubular fender piles using MS plates of 10mm thick with 6mm thick wrapper plate including cost of all material, labour, tools, equipments etc. Complete as per detailed specifications, drawing and directions of the Engineer-in-Charge.	10000.00	One Kilogram	211.30	Rupees Two Hundred Eleven and Thirty Paise Only	2113000.00	Rupees Twenty One Lakh Thirteen Thousand Only
2	Providing Filling inside the tubular fender piles with crusher run screening including compacting, cost of all materials, labour, tools, equipmenmts etc. complete as per detailed specifications and directions of the Engineer-in-Charge.	25.00	One Cubic Metre	3852.50	Rupees Three Thousand Eight Hundred Fifty Two and Fifty Paise Only	96312.50	Rupees Ninety Six Thousand Three Hundred Twelve and Fifty Paise Only

SL.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Providing M15 grade cement concrete using 20mm graded metal for plugging the pile top including, compacting curing, cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-Charge.	0.50	One Cubic Metre	10,700.75	Rupees Ten Thousand Seven Hundred and Seventy Five Paise Only	5350.38	Rupees Five Thousand Three Hundred Fifty and Thirty Seven Paise Only
4	Painting the outer surface of the tubular fender piles with one coat of primer and two coats of coal tar Epoxy paint including cost of all labour, materials, tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-Charge	100.00	One Square Metre	257.88	Rupees Two Hundred Fifty Seven and Eighty Eight Paise Only	25788.00	Rupees Twenty Five Thousand Seven Hundred Eighty Eight Only
5	Transporting, pitching and driving the fender piles in position at IOCL Fine Arts Jetty at Ernakulam including cost of all labour, tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-Charge.	4.00	Each	64557.54	Rupees Sixty Four Thousand Five Hundred Fifty Seven and Fifty Four Paise Only	258230.16	Rupees Two Lakh Fifty Eight Thousand Two Hundred Thirty and Sixteen Paise Only
	Total Part-A					2498681.04	
B	PART.B. PROVIDING & FIXING LADER AT MULT (MD-4)						

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Dismantling steel work in builtup sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50metres lead including cost of all labour, equipments, toos etc. complete as per detailed specifications and directions of the Engieer-in-Charge.	1100.00	Kilogram	5.08	Rupees Five and Eight Paise Only	5588.00	Rupees Five Thousand Five Hundred Eighty Eight Only
2	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works including cost of all labour, materials, equipments, tools etc. complete as per detailed specifications and directions of the Engieer-in-Charge.	1100.00	Kilogram	127.27	Rupees One Hundred Twenty Seven and Twenty Seven Paise Only	139997.00	Rupees One Lakh Thirty Nine Thousand Nine Hundred Ninety Seven Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Providing and fixing Stainless steel (SS - 316) Mooring Rings of outer dia 200mm, using 25mm dia rod including welding with suitable electrodes, fixing the same to the stainless steel 400mm long eye hook cut out off 32mm dia bar fixed at the face of the jetty etc. complete as per drawings, detailed specifications & directions of the Engineer in charge	4.00	Each	15000	Rupees Fifteen Thousand Only	60000.00	Rupees Sixty Thousand Only
4	Transporting surplus materials and debris using Mini tipper lorry (3 M3), dumping and levelling within a lead of 6Km including all labour and consumables etc as per the directions of the Engineer-in-charge.	1.00	One Square Metre	4,841.00	Rupees Four Thousand Eight Hundred Forty One Only	4841.00	Rupees Four Thousand Eight Hundred Forty One Only
5	Supplying and fixing 5.8 grade fully treaded GI anchor rod M12x120mm upto a minimum chemical anchoring of 90mm in concrete with Hilti HY170 or approved equivalent chemical including costof of all labour,materials, consumables, plants, power and application cost etc. complete	50.00	Each	205.00	Rupees Two Hundred Five Only	10250.00	Rupees Ten Thousand Two Hundred Fifty Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
6	Painting with aluminium paint of approved brand and manufacture to give an even shade. Two or more coats on new work	100.00	One Square Metre	152.55	Rupees One Hundred Fifty Two and Fifty Five Paise Only	15255.00	Rupees Fifteen Thousand Two Hundred Fifty Five Only
	Total amount for Part-B					235931.00	
	Total amount for Part-A & Part B					2734612.04	

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
BIDDER'S QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail			2734612.04			
" This is a Electronic Submission No Need of Signature"							