

COCHIN PORT AUTHORITY					
GOVT OF INDIA					
BOQ - 2 TR & 1.5 TR SPLIT HIGHWALL AC					
Sl. No.	Description	Qty	UOM	Rate	AMOUNT
<b>SUPPLY</b>					
1	Supply of 2 TR High wall Inverter split AC with BEE 5 star rating, Copper Coils etc. including 3 mtrs copper refrigerant piping.	4	Nos		
2	Supply of 1.5 TR High wall Inverter split AC with BEE 5 star rating, Copper Coils etc. including 3 mtrs copper refrigerant piping.	4	Nos		
3	SITC of wall mounted Heavy support for ODU of AC	8	Nos		
4	Installation charges	8	Nos		
5	SITC of Hard/Soft copper Refrigerant piping, complete with fittings, elbows, bends, supporting arrangement on walls <b>beyond 3 mtrs</b>	1	MTR		
6	Supply & Installation of insulated PVC drain pipe of 25mm dia	1	MTR		
7	SITC of 5 KVA stabilizer	4	Nos		
8	SITC of 4 KVA stabilizer	4	Nos		
9	Supply & Laying of CU PVC sheathed flexible cable if necessary	1	MTR		
10	Core Cutting	1	Nos		
<b>TOTAL</b>					

NB: GST IF ANY SHALL BE MENTIONED