

**COCHIN PORT AUTHORITY**  
An ISO-9001:2008 & ISPS Compliant Port

**ADDENDUM / CORRIGENDUM NO.6**

**TENDER FOR  
RECONSTRUCTION OF Q2-Q3 BERTHS AT MATTANCHERRY WHARF OF COCHIN  
PORT (RETENDER)  
(Tender No.T10/T-2093/2026-C)**

The following clauses in the Bid Document stand renumbered / modified / replaced / added / deleted as below:

Sl. No.	Reference Clause No.	Section / Volume	Renumbered as / Modified as / Replaced with / additional details / deleted							
1	Sl. No.19 of Addendum- 4	Addendum 4, Page No.8 & 9	<b><u>Sl.No.19 of Addendum – 4</u></b>							
			Sl. No.	Sub- heads and items of work	Approximate Quantity	Unit	Departmental Rate (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
			7	Transporting the fabricated MS liners fabricated as per item No. 6 above from the fabrication yard to pile location, handling, pitching and driving the MS liners to required level and verticality including setting piling rigs/ gantry in position, temporary works for driving piles etc. complete all as per detailed specifications and directions of the Engineer-in – charge.	1050	Nos.	36,501.00	Rupees Thirty Six Thousand Five Hundred One Only	38,32,605.00	Rupees Thirty Eight Lakh Thirty Two Thousand Six Hundred Five Only
<b><u>Sl.No.19 of Addendum – 4 is replaced as</u></b>										
			Sl. No.	Sub- heads and items of work	Approximate Quantity	Unit	Departmental Rate (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
			7	Transporting the fabricated MS liners fabricated as per item No.6 above from the fabrication yard to pile location, handling, pitching	105.00	Nos.	36,501.00	Rupees Thirty Six Thousand Five Hundred One Only	38,32,605.00	Rupees Thirty Eight Lakh Thirty Two Thousand Six Hundred Five Only

All Addendum/ Corrigendum shall form part of the Bid Document and shall be duly signed and submitted along with the Bid by the Bidder

			and driving the MS liners to required level and verticality including setting piling rigs/ gantry in position, temporary works for driving piles etc. complete all as per detailed specifications and directions of the Engineer-in-charge.							
2	Sl. No.20 of Addendum- 4	Addendum 4, Page No.10 & 11	<b><u>Sl.No.20 of Addendum - 4</u></b>							
			Sl. No.	Sub- heads and items of work	Approximate Quantity	Unit	Departmental Rate (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
			23	Supply and application of Rearm Crete FC putty Build, first coat Epilux 9 IPN coating grey (airless spray / brush)- 50 microns, second & third coat Epilux 9 HB phenolic IPN coating light grey (airless spray/ brush)- 100 microns each, finishing coat Berger thane IPN coating dark grey (airless spray/ brush)-50 microns as per drawing and specifications including manpower, paint, consumables, scaffolding fixing and removing, cleaning and preparing surfaces with sand paper if necessary or by any other approved means etc., tools & tackles, power tooling (grinding), pontoon, electricity, steel rod cutting, safety PPE's, overheads, etc. complete	7354.00	m <sup>2</sup>	1,485.00	Rupees One Thousand Four Hundred Eighty Five Only		Rupees One Crore Nine Lakh Twenty Thousand Six Hundred Ninety Only

<b>is replaced as</b>							
<b><u>SI.No.20 of Addendum - 4</u></b>							
Sl. No.	Sub- heads and items of work	Approximate Quantity	Unit	Departmental Rate (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
23	Supply and application of Rearm Crete FC putty Build, first coat two pack IPN technology based epoxy coating/sealer grey (airless spray / brush)- 50 microns, second & third coat two pack IPN technology based Epoxy coating light grey (airless spray/ brush)- 100 microns each, finishing coat two pack aliphatic polyurethane IPN coating dark grey (airless spray/ brush)-50 microns as per drawing and specifications including manpower, paint, consumables, scaffolding fixing and removing, cleaning and preparing surfaces with sand paper if necessary or by any other approved means etc., tools & tackles, power tooling (grinding), pontoon, electricity, steel rod cutting, safety PPE's, overheads, etc. complete	7354.00	m <sup>2</sup>	1,485.00	Rupees One Thousand Four Hundred Eighty Five Only	1,09,20,690.00	Rupees One Crore Nine Lakh Twenty Thousand Six Hundred Ninety Only
3	Section-V	<b><u>New Clause under Section-V is added as Appendix-I:</u></b> <b>PREAMBLE</b>					

Sd/-

**CHIEF ENGINEER**