

| COCHIN PORT AUTHORITY                                                      |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                      |                                    |                                                                            |                            |                                                                               |
|----------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------------------|------------------------------------|----------------------------------------------------------------------------|----------------------------|-------------------------------------------------------------------------------|
| www.tenderwizard.com/CPT                                                   |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                      |                                    |                                                                            |                            |                                                                               |
| Tender No: T6/T-2112/2026-C Dated: 16-09-2026                              |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                      |                                    |                                                                            |                            |                                                                               |
| Name of Work : RENOVATION OF COCHIN PORT OFFICER'S SILVER JUBILEE BUILDING |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                      |                                    |                                                                            |                            |                                                                               |
| SCHEDULE – "II"- SCHEDULE OF QUANTITIES OF WORK TO BE DONE ON CONTRACT     |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                      |                                    |                                                                            |                            |                                                                               |
| Name and Address of the Vendor:                                            |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |      |                      |                                    |                                                                            |                            |                                                                               |
| Sl. No.                                                                    | Sub- heads and items of work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         | Unit | Approximate Quantity | Departmental Rate/ unit Price (Rs) | Departmental Rate in Words                                                 | Departmental Amount in Rs. | Departmental Amount in Words                                                  |
| 1                                                                          | Dismantling W.C. Pan/ Wash basin of all sizes including disposal of dismantled materials i/c malba all complete as per directions of Engineer-in-charge. Rate inclusive of labour, sundries, tools etc                                                                                                                                                                                                                                                                                                                                                               | Each | 4.00                 | 149.28                             | Rupees One Hundred Forty Nine and Twenty Eight Paise Only                  | 597.13                     | Rupees Five Hundred Ninety Seven and Twelve Paise Only                        |
| 2                                                                          | Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineer in-charge. Rate inclusive of labour, sundries, tools etc                                                                                                                                                                                                                                                                                  | m2   | 130.00               | 62.73                              | Rupees Sixty Two and Seventy Two Paise Only                                | 8154.90                    | Rupees Eight Thousand One Hundred Fifty Four and Ninety Paise Only            |
| 3                                                                          | Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar, Rate inclusive of labour, sundries, tools etc                                                                                                                                                                                                                                                                                                 | m3   | 1.50                 | 2293.44                            | Rupees Two Thousand Two Hundred Ninety Three and Forty Three Paise Only    | 3440.16                    | Rupees Three Thousand Four Hundred Forty and Sixteen Paise Only               |
| 4                                                                          | Dismantling doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead : of area 3 sq. metres and below. Rate inclusive of labour, sundries, tools etc                                                                                                                                                                                                                                                                                                                | Each | 6.00                 | 408.77                             | Rupees Four Hundred Eight and Seventy Seven Paise Only                     | 2452.62                    | Rupees Two Thousand Four Hundred Fifty Two and Sixty Two Paise Only           |
| 5                                                                          | Brick work with common burnt clay machine moulded perforated bricks of class designation 12.5 conforming to IS: 2222 in superstructure above plinth level up to floor five level in cement mortar 1:6 (1 cement : 6 coarse sand) : With F.P.S.(non modular) bricks. Rate incl of all material,labour, sundries etc                                                                                                                                                                                                                                                   | m3   | 2.10                 | 10352.74                           | Rupees Ten Thousand Three Hundred Fifty Two and Seventy Four Paise Only    | 21740.75                   | Rupees Twenty One Thousand Seven Hundred Forty and Seventy Five Paise Only    |
| 6                                                                          | 12 mm cement plastering of cement mortar 1:4 (1 cement: 4 fine sand),Rate incl of all material,labour, sundries etc Rate incl of all material,labour, sundries etc                                                                                                                                                                                                                                                                                                                                                                                                   | m2   | 32.00                | 386.34                             | Rupees Three Hundred Eighty Six and Thirty Three Paise Only                | 12362.88                   | Rupees Twelve Thousand Three Hundred Sixty Two and Eighty Eight Paise Only    |
| 7                                                                          | Dismantling tile work in floors and roofs laid in cement mortar including stacking materials within 50metres lead, for thickness of tiles 10mm to 25mm as directed by Engineer in-charge. Rate inclusive of labour, sundries, tools etc                                                                                                                                                                                                                                                                                                                              | m2   | 27.00                | 81.71                              | Rupees Eighty One and Seventy Paise Only                                   | 2206.17                    | Rupees Two Thousand Two Hundred Six and Seventeen Paise Only                  |
| 8                                                                          | Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge. Rate inclusive of labour, sundries, tools etc                                                                                                                                                                                                                                                                                                                         | m3   | 0.30                 | 3953.29                            | Rupees Three Thousand Nine Hundred Fifty Three and Twenty Eight Paise Only | 1185.99                    | Rupees One Thousand One Hundred Eighty Five and Ninety Eight Paise Only       |
| 9                                                                          | 12 mm cement plastering of cement mortar 1:4 (1 cement: 4 fine sand),Rate incl of all material,labour, sundries etc Rate incl of all material,labour, sundries etc                                                                                                                                                                                                                                                                                                                                                                                                   | m2   | 23.00                | 386.34                             | Rupees Three Hundred Eighty Six and Thirty Three Paise Only                | 8885.82                    | Rupees Eight Thousand Eight Hundred Eighty Five and Eighty Two Paise Only     |
| 10                                                                         | Providing and laying Vitrified tiles in different sizes (thickness to be specified by the manufacturer), with water absorption less than 0.08% and conforming to IS: 15622, of approved brand & manufacturer, in all colours and shade, in skirting, riser of steps, laid with cement based high polymer modified quick set tile adhesive (water based) conforming to IS: 15477, in average 6 mm thickness, including grouting of joints (Payment for grouting of joints to be made separately). Size of Tile 800x800 mm . incl of all material,labour, sundries etc | m2   | 28.00                | 2481.62                            | Rupees Two Thousand Four Hundred Eighty One and Sixty Two Paise Only       | 69485.36                   | Rupees Sixty Nine Thousand Four Hundred Eighty Five and Thirty Six Paise Only |
| 11                                                                         | Fixing chowkhat in existing opening in brick/ RCC wall with dash fasteners/ Chemical fasteners of appropriate size (3 nos on each vertical member of door chowkhat and 2 nos on each vertical member of window chowkhats), including Cost of dash fasteners/ chemical fastener.                                                                                                                                                                                                                                                                                      | Each | 3.00                 | 241.68                             | Rupees Two Hundred Forty One and Sixty Seven Paise Only                    | 725.04                     | Rupees Seven Hundred Twenty Five and Four Paise Only                          |
| 12                                                                         | Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 800x800 mm. incl of all material,labour, sundries etc                                                               | m2   | 30.00                | 2098.96                            | Rupees Two Thousand Ninety Eight and Ninety Five Paise Only                | 62968.80                   | Rupees Sixty Two Thousand Nine Hundred Sixty Eight and Eighty Paise Only      |

|    |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                         |      |         |         |                                                                |           |                                                                             |
|----|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|---------|---------|----------------------------------------------------------------|-----------|-----------------------------------------------------------------------------|
| 13 | Grouting the joints of flooring tiles having joints of 3 mm width, using epoxy grout mix of 0.70 kg of organic coated filler of desired shade (0.10 kg of hardener and 0.20 kg of resin per kg), including filling / grouting and finishing complete as per direction of Engineer-in charge. Size of Tile 800x800 mm. incl of all material,labour, sundries etc                                                                                                                                                                                                                                                                         | m2   | 60.00   | 272.46  | Rupees Two Hundred Seventy Two and Forty Five Paise Only       | 16347.60  | Rupees Sixteen Thousand Three Hundred Forty Seven and Sixty Paise Only      |
| 14 | Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.incl of all material,labour, sundries etc                                                                                                                                                                                                                                                                                                                                                                              | Kg   | 1300.00 | 148.84  | Rupees One Hundred Forty Eight and Eighty Three Paise Only     | 193492.00 | Rupees One Lakh Ninety Three Thousand Four Hundred Ninety Two Only          |
| 15 | Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.On steel work .incl of material, labour, sundries of both priming coat and epoxy painting etc.                                                                                                                                                                                                                                                                                                                                      | m2   | 90.00   | 269.12  | Rupees Two Hundred Sixty Nine and Eleven Paise Only            | 24220.80  | Rupees Twenty Four Thousand Two Hundred Twenty and Eighty Paise Only        |
| 16 | Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid, Make CERA or Approved equivalent.The rate is inclusive of material, material carriage ,sundries etc. | Each | 2.00    | 8913.03 | Rupees Eight Thousand Nine Hundred Thirteen and Two Paise Only | 17826.06  | Rupees Seventeen Thousand Eight Hundred Twenty Six and Six Paise Only       |
| 17 | Providing and fixing 15mm nominal bore C.P. brass angle valve for Wash basin, Flush tank and Health faucet of approved quality conforming to IS:8931, rate incl of all accessories, fitting charges,sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                        | Nos  | 6.00    | 639.32  | Rupees Six Hundred Thirty Nine and Thirty One Paise Only       | 3835.92   | Rupees Three Thousand Eight Hundred Thirty Five and Ninety Two Paise Only   |
| 18 | Supplying good quality Health Faucets of Parryware T9940A1 Slimline with SS Hose & Hook or approved equivalent make including all required fitting etc.Complete.                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | Each | 2.00    | 676.50  | Rupees Six Hundred Seventy Six and Fifty Paise Only            | 1353.00   | Rupees One Thousand Three Hundred Fifty Three Only                          |
| 19 | Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap .rate incl of all accessories, fitting charges,sundries etc                                                                                                                                                                                                                                           | Each | 2.00    | 2091.94 | Rupees Two Thousand Ninety One and Ninety Four Paise Only      | 4183.88   | Rupees Four Thousand One Hundred Eighty Three and Eighty Eight Paise Only   |
| 20 | Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and eighing not less than 690 gms. 15 mm nominal bore, rate incl of all accessories, fitting charges,sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                     | Each | 2.00    | 889.40  | Rupees Eight Hundred Eighty Nine and Thirty Nine Paise Only    | 1778.80   | Rupees One Thousand Seven Hundred Seventy Eight and Seventy Nine Paise Only |
| 21 | Providing and fixing PTMT Waste Coupling for wash basin and sink, of approved quality and colour. Waste coupling 38 mm dia of 83 mm length and 77mm breadth, weighing not less than 60 gms.rate incl of all accessories,carriages& fitting charges etc                                                                                                                                                                                                                                                                                                                                                                                  | Each | 2.00    | 136.26  | Rupees One Hundred Thirty Six and Twenty Five Paise Only       | 272.52    | Rupees Two Hundred Seventy Two and Fifty Two Paise Only                     |
| 22 | Providing and fixing PTMT towel ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms.rate incl of all accessories, carriages & fitting charges etc.                                                                                                                                                                                                                                                                                                                                         | Each | 4.00    | 258.21  | Rupees Two Hundred Fifty Eight and Twenty Paise Only           | 1032.84   | Rupees One Thousand Thirty Two and Eighty Three Paise Only                  |
| 23 | Providing and fixing PTMT soap Dish Holder having length of 138mm, breadth 102mm, height of 75mm with concealed fitting arrangements, weighing not less than 106 gms.rate incl of all accessories, carriages & fitting charges etc                                                                                                                                                                                                                                                                                                                                                                                                      | Nos  | 2.00    | 124.07  | Rupees One Hundred Twenty Four and Six Paise Only              | 248.14    | Rupees Two Hundred Forty Eight and Fourteen Paise Only                      |
| 24 | Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end). 32 mm nominal bore..rate incl of all accessories, carriages & fitting charges etc                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Nos  | 2.00    | 767.67  | Rupees Seven Hundred Sixty Seven and Sixty Six Paise Only      | 1535.34   | Rupees One Thousand Five Hundred Thirty Five and Thirty Three Paise Only    |
| 25 | Supplying, Laying and jointing PVC pipe (class5) with ISI mark including all specials for water supply line. c. 32 mm dia , rate incl of all accessories, carriages & fitting charges etc                                                                                                                                                                                                                                                                                                                                                                                                                                               | m    | 20.00   | 97.40   | Rupees Ninety Seven and Forty Paise Only                       | 1948.00   | Rupees One Thousand Nine Hundred Forty Eight Only                           |
| 26 | Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.Concealed work, including cutting chases and making good the walls etc . 25 mm nominal outer dia Pipes.                                                                                  | m    | 20.00   | 698.26  | Rupees Six Hundred Ninety Eight and Twenty Six Paise Only      | 13965.20  | Rupees Thirteen Thousand Nine Hundred Sixty Five and Twenty Paise Only      |
| 27 | Supplying and laying/fixing 63mm dia. PVC pipe (class2) buried /above ground for drainage disposal.rate incl of all accessories, carriages & fitting charges etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                        | m    | 20.00   | 172.50  | Rupees One Hundred Seventy Two and Fifty Paise Only            | 3450.00   | Rupees Three Thousand Four Hundred Fifty Only                               |
| 28 | Supplying and laying/fixing 110mm dia. PVC pipe (class2) buried/ above ground for drainage disposal. rate incl of all accessories, carriages & fitting charges etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | m    | 15.00   | 338.80  | Rupees Three Hundred Thirty Eight and Eighty Paise Only        | 5082.00   | Rupees Five Thousand Eighty Two Only                                        |

|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                  |                                                                      |           |                                                                        |               |                                                                                    |
|---------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------|----------------------------------------------------------------------|-----------|------------------------------------------------------------------------|---------------|------------------------------------------------------------------------------------|
| 29      | Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross-section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness. The laminate shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat. Door frame laminate shall be 2mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame. rate incl of material, labour , sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | m                                | 10.00                                                                | 635.59    | Rupees Six Hundred Thirty Five and Fifty Eight Paise Only              | 6355.90       | Rupees Six Thousand Three Hundred Fifty Five and Ninety Paise Only                 |
| 30      | Providing and fixing to existing door frames 30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames.rate incl of material, labour , sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                            | m2                               | 4.00                                                                 | 4141.98   | Rupees Four Thousand One Hundred Forty One and Ninety Seven Paise Only | 16567.92      | Rupees Sixteen Thousand Five Hundred Sixty Seven and Ninety Two Paise Only         |
| 31      | Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on interlocking metal grid of hot dipped galvanized steel sections ( galvanized @ 120 grams/ sqm, both side inclusive) consisting of main 6T6 runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross 6T6 of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main 6T6 at 600 mm center to center to form a grid of 1200x600 mm and secondary cross 6T6 of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main 6T6 runners to be c | m2                               | 80.00                                                                | 1992.03   | Rupees One Thousand Nine Hundred Ninety Two and Three Paise Only       | 159362.40     | Rupees One Lakh Fifty Nine Thousand Three Hundred Sixty Two and Forty Paise Only   |
| 32      | Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete. Incl labour, sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      | m2                               | 650.00                                                               | 28.00     | Rupees Twenty Seven and Ninety Nine Paise Only                         | 18200.00      | Rupees Eighteen Thousand Two Hundred Only                                          |
| 33      | Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer,over the plastered wall surface to prepare the surface even and smooth complete. Rate incl of all material,labour, sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     | m2                               | 650.00                                                               | 173.72    | Rupees One Hundred Seventy Three and Seventy One Paise Only            | 112918.00     | Rupees One Lakh Twelve Thousand Nine Hundred Eighteen Only                         |
| 34      | Applying priming coats with primer of approved brand and manufacture, having low VOC (Volatile Organic Compound ) content. With water thinnable cement primer on wall surface having VOC content less than 50 grams/litre.rate incl of material, labour , sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | m2                               | 650.00                                                               | 82.32     | Rupees Eighty Two and Thirty Two Paise Only                            | 53508.00      | Rupees Fifty Three Thousand Five Hundred Eight Only                                |
| 35      | Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound ) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour.Two coats. .rate incl of material, labour , sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                 | m2                               | 650.00                                                               | 158.97    | Rupees One Hundred Fifty Eight and Ninety Six Paise Only               | 103330.50     | Rupees One Lakh Three Thousand Three Hundred Thirty and Fifty Paise Only           |
| 36      | Painting with synthetic enamel paint of approved brand and manufacture to give an even shade :Two or more coats on new work.rate incl of material, labour , sundries etc                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | m2                               | 80.00                                                                | 173.55    | Rupees One Hundred Seventy Three and Fifty Four Paise Only             | 13884.00      | Rupees Thirteen Thousand Eight Hundred Eighty Four Only                            |
| 37      | Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved. rate incl of carriage of materials etc.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | m3                               | 20.00                                                                | 293.83    | Rupees Two Hundred Ninety Three and Eighty Three Paise Only            | 5876.60       | Rupees Five Thousand Eight Hundred Seventy Six and Sixty Paise Only                |
|         | GRAND TOTAL                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       |                                  |                                                                      |           |                                                                        | ₹ 9,74,781.03 | Rupees Nine Lakh Seventy Four Thousand Seven Hundred Eighty One and Two Paise Only |
|         | BIDDER'S QUOTING AREA                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                             |                                  |                                                                      |           |                                                                        |               |                                                                                    |
| Sl. No. | Description of Work: RENOVATION OF COCHIN PORT OFFICER'S SILVER JUBILEE BUILDING                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                  | Departmental Estimated Cost (Rs) | Percentage Quoted above/ below the Departmental Amount by the Bidder |           | Above/Below                                                            |               |                                                                                    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                  | * In Figures                                                         | *In Words |                                                                        |               |                                                                                    |
|         | Percenatge Quoted above / below the Departmental Amount shown in the above Schedule                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                               | 9,74,781.03                      |                                                                      |           |                                                                        |               |                                                                                    |
|         |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                   |                                  |                                                                      |           |                                                                        |               |                                                                                    |
|         | * Note                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            |                                  |                                                                      |           |                                                                        |               |                                                                                    |
|         | 1. The Tenderer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                     |                                  |                                                                      |           |                                                                        |               |                                                                                    |
|         | 2. Only two decimal digits shall be accepted                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                      |                                  |                                                                      |           |                                                                        |               |                                                                                    |
|         | 3. Tenderers shall also quote Above/ Below in words themselves in the last column.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                |                                  |                                                                      |           |                                                                        |               |                                                                                    |
|         | 4.In case of discrepancy in words and figures the quoted figure in words shall prevail.                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           |                                  |                                                                      |           |                                                                        |               |                                                                                    |