

COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Tender No: T10/T-2117/2026-C

Name of Work: RECONSTRUCTION OF MARAR ROAD AND G V IYER ROAD WITH CC PAVER BLOCKS, RCC DRAINS, BOX CULVERTS, UTILITY DUCTS ETC., AT W/ISLAND.

SCHEDULE – “II”- SCHEDULE OF QUANTITIES OF WORK TO BE DONE ON CONTRACT

Name and Address of the Vendor:							
Sl. No.	Sub- heads and items of work	Unit	Approximate Quantity	Departmental Rate/ Unit Price (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
	PART-A: RECONSTRUCTION OF MARAR ROAD						
A1	PART-A1: CONSTRUCTION OF NEW DRAINS WITH ELECTRICAL CABLE DUCT & DATA CABLE DUCT AND ROAD CROSSING BOX CULVERTS FOR MARAR ROAD AT W/ISLAND.						
1	Demolishing the existing R.C.C works manually/ by mechanical means including stacking of retrieved steel reinforcement bars at the loactions pointed out by the Engineer-in-charge and disposal of unserviceable material within 50metres lead as per detailed specifications and directions of the Engineer - in- charge.	m ³	350.00	3,953.29	Rupees Three Thousand Nine Hundred Fifty Three and Twenty Nine Paise Only	13,83,651.50	Rupees Thirteen Lakh Eighty Three Thousand Six Hundred Fifty One and Fifty Paise Only
2	Earth work in excavation in all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m as per drawings, detailed specifications and directions of the Engineer-in-charge.	m ³	1,442.00	289.77	Rupees Two Hundred Eighty Nine and Seventy Seven Paise Only	4,17,848.34	Rupees Four Lakh Seventeen Thousand Eight Hundred Forty Eight and Thirty Four Paise Only
3	Dismantling of the existing flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 3 kilometre, as per detailed specification and directions of Engineer-in-charge.	m ³	31.00	468.44	Rupees Four Hundred Sixty Eight and Forty Four Paise Only	14,521.64	Rupees Fourteen Thousand Five Hundred Twenty One and Sixty Four Paise Only
4	Taking out existing CC interlocking paver blocks from footpath/ central verge, including removal of rubbish etc., stacking of serviceable materials at the loactions pointed out by the Engineer-in-charge and disposal of unserviceable material within 50 metres lead as per detailed specifications and directions of Engineer - in- charge.	m ²	5.00	146.67	Rupees One Hundred Forty Six and Sixty Seven Paise Only	733.35	Rupees Seven Hundred Thirty Three and Thirty Five Paise Only
5	Supplying and stacking good quality cut gravel/Red Earth as per detailed specifications and directions of the Engineer-in-Charge.	m ³	326.00	1,500.00	Rupees One Thousand Five Hundred Only	4,89,000.00	Rupees Four Lakh Eighty Nine Thousand Only
6	Providing and laying in position cement concrete of 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) up to plinth level including levelling, compacting, curing etc. complete excluding the cost of centering and shuttering as per drawings, detailed specifications and directions of the Engineer - in- charge.	m ³	552.00	8,120.53	Rupees Eight Thousand One Hundred Twenty and Fifty Three Paise Only	44,82,532.56	Rupees Forty Four Lakh Eighty Two Thousand Five Hundred Thirty Two and Fifty Six Paise Only
7	Providing and laying in position reinforced cement concrete of grade 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources), including levelling, compacting and curing, excluding the cost of centering, shuttering and reinforcement, as per drawings, detailed specifications and directions of the Engineer-in-charge.	m ³	1,522.00	10,069.82	Rupees Ten Thousand Sixty Nine and Eighty Two Paise Only	1,53,26,266.04	Rupees One Crore Fifty Three Lakh Twenty Six Thousand Two Hundred Sixty Six and Four Paise Only

Sl. No.	Sub- heads and items of work	Unit	Approximate Quantity	Departmental Rate/ Unit Price (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
8	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work of M25 grade with minimum cement content of 330 kg /cum using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per drawings, detailed specifications and directions of the Engineer-in-Charge. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.	m ³	51.00	10,580.78	Rupees Ten Thousand Five Hundred Eighty and Seventy Eight Paise Only	5,39,619.78	Rupees Five Lakh Thirty Nine Thousand Six Hundred Nineteen and Seventy Eight Paise Only
9	Steel reinforcement for R.C.C. work using thermo-Mechanically Treated bars of grade Fe-500D or more including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per drawings, detailed specifications and directions of the Engineer-in-charge.	kg	1,48,120.00	120.06	Rupees One Hundred Twenty and Six Paise Only	1,77,83,287.20	Rupees One Crore Seventy Seven Lakh Eighty Three Thousand Two Hundred Eighty Seven and Twenty Paise Only
10	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns as per drawings, detailed specifications and directions of the Engineer-in-charge..	m ²	9,763.00	436.55	Rupees Four Hundred Thirty Six and Fifty Five Paise Only	42,62,037.65	Rupees Forty Two Lakh Sixty Two Thousand Thirty Seven and Sixty Five Paise Only
11	Supplying and laying/ fixing 110mm OD PVC pipe(class 2) buried/ above ground for drainage disposal as per drawings, detailed specifications and directions of the Engineer-in-charge.	m	178.00	338.80	Rupees Three Hundred Thirty Eight and Eighty Paise Only	60,306.40	Rupees Sixty Thousand Three Hundred Six and Forty Paise Only
	Total for Part A1					4,47,59,804.46	
A2	PART-A2: RECONSTRUCTION OF MARAR ROAD WITH PAVER BLOCKS AT W/ISLAND						
1	Scarifying metalled (water-bound) road surface including disposal of rubbish, lead upto 50 m and consolidation of the aggregate received from scarifying with power road roller of 8 to 10 tonne capacity as per detailed specifications and directions of Engineer - in-charge.	m ²	6,300.00	37.07	Rupees Thirty Seven and Seven Paise Only	2,33,541.00	Rupees Two Lakh Thirty Three Thousand Five Hundred Forty One Only
2	Providing, laying, spreading and compacting with graded stone aggregate (size range 53 mm to 0.075 mm) (wet mix macadam (WMM)) including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	m ³	950.00	3,244.23	Rupees Three Thousand Two Hundred Forty Four and Twenty Three Paise Only	30,82,018.50	Rupees Thirty Lakh Eighty Two Thousand Eighteen and Fifty Paise Only
3	Providing and laying factory made 100mm thick Cement Concrete paver blocks of M-40 grade made by table vibratory method, to attain superior smooth finish using PU or equivalent moulds, laid in required colour & pattern over 50mm thick compacted bed of 6mm coarse aggregate, compacting and proper embedding / laying of inter locking paver blocks into the 6mm coarse aggregate bedding layer through vibratory compaction by using plate vibrator, filling the joints with crusher sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in drive ways or light traffic parking etc. all complete as per drawings, manufacturer's specifications & direction of the Engineer-in-Charge.	m ²	6,300.00	1,280.00	Rupees One Thousand Two Hundred Eighty Only	80,64,000.00	Rupees Eighty Lakh Sixty Four Thousand Only
4	Providing and laying in position cement concrete of grade 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources, excluding the cost of centering and shuttering as per detailed specifications and directions of the Engineer - in- charge.	m ³	35.00	9,285.12	Rupees Nine Thousand Two Hundred Eighty Five and Twelve Paise Only	3,24,979.20	Rupees Three Lakh Twenty Four Thousand Nine Hundred Seventy Nine and Twenty Paise Only

Sl. No.	Sub- heads and items of work	Unit	Approximate Quantity	Departmental Rate/ Unit Price (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
5	Manufacturing, supplying and fixing retro reflective sign boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing , specification and direction of Engineer-in-charge. Mandatory/ Regulatory sign boards of 900 mm diameter with support length of 3750 mm.	Each	8.00	7,996.58	Rupees Seven Thousand Nine Hundred Ninety Six and Fifty Eight Paise Only	63,972.64	Rupees Sixty Three Thousand Nine Hundred Seventy Two and Sixty Four Paise Only
6	Manufacturing, supplying and fixing retro reflective sign boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing , specification and direction of Engineer-in-charge. Cautionary /warning sign boards of equilateral triangular shape having each side of 900 mm with support length of 3650 mm.	Each	8.00	6,189.17	Rupees Six Thousand One Hundred Eighty Nine and Seventeen Paise Only	49,513.36	Rupees Forty Nine Thousand Five Hundred Thirteen and Thirty Six Paise Only
Total for Part A2						1,18,18,024.70	
PART-B: RECONSTRUCTION OF GV IYER ROAD							
B1	PART-B1: CONSTRUCTION OF NEW DRAINS WITH ELECTRICAL CABLE DUCT & DATA CABLE DUCT AND ROAD CROSSING BOX CULVERTS FOR GV IYER ROAD AT W/ISLAND						
1	Demolishing the existing R.C.C. works manually/ by mechanical means including stacking of retrieved steel reinforcement bars at the loactions pointed out by the Engineer-in-charge and disposal of unserviceable material within 50 metres lead as per detailed specifications and directions of the Engineer - in- charge.	m ³	118.00	3,953.29	Rupees Three Thousand Nine Hundred Fifty Three and Twenty Nine Paise Only	4,66,488.22	Rupees Four Lakh Sixty Six Thousand Four Hundred Eighty Eight and Twenty Two Paise Only

Sl. No.	Sub- heads and items of work	Unit	Approximate Quantity	Departmental Rate/ Unit Price (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
2	Earth work in excavation in all kinds of soil by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m as per drawings, detailed specifications and directions of the Engineer-in-charge..	m ³	891.00	289.77	Rupees Two Hundred Eighty Nine and Seventy Seven Paise Only	2,58,185.07	Rupees Two Lakh Fifty Eight Thousand One Hundred Eighty Five and Seven Paise Only
3	Dismantling of the existing flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 3 kilometre, as per detailed specification and directions of Engineer-in-charge.	m ³	9.00	468.44	Rupees Four Hundred Sixty Eight and Forty Four Paise Only	4,215.96	Rupees Four Thousand Two Hundred Fifteen and Ninety Six Paise Only
4	Supplying and stacking good quality cut gravel/Red Earth as per detailed specifications and directions of the Engineer-in-Charge.	m ³	163.00	1,500.00	Rupees One Thousand Five Hundred Only	2,44,500.00	Rupees Two Lakh Forty Four Thousand Five Hundred Only
5	Providing and laying in position cement concrete of 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources) up to plinth level including levelling, compacting, curing etc. complete excluding the cost of centering and shuttering as per drawings, detailed specifications and directions of the Engineer - in- charge.	m ³	272.00	8,120.53	Rupees Eight Thousand One Hundred Twenty and Fifty Three Paise Only	22,08,784.16	Rupees Twenty Two Lakh Eight Thousand Seven Hundred Eighty Four and Sixteen Paise Only
6	Providing and laying in position reinforced cement concrete of grade 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources), including levelling, compacting and curing, excluding the cost of centering, shuttering and reinforcement, as per drawings, detailed specifications and directions of the Engineer-in-charge.	m ³	783.00	10,069.82	Rupees Ten Thousand Sixty Nine and Eighty Two Paise Only	78,84,669.06	Rupees Seventy Eight Lakh Eighty Four Thousand Six Hundred Sixty Nine and Six Paise Only
7	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work of M25 grade with minimum cement content of 330 kg /cum, using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana / Ordinary Portland /Portland Slag cement, admixtures in recommended proportions as per IS: 9103 to accelerate / retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per drawings, detailed specifications and directions of the Engineer-in-Charge. Note: Extra cement up to 10% of the minimum specified cement content in design mix shall be payable separately. In case the cement content in design mix is more than 110% of the specified minimum cement content, the contractor shall have discretion to either re-design the mix or bear the cost of extra cement.	m ³	15.00	10,580.78	Rupees Ten Thousand Five Hundred Eighty and Seventy Eight Paise Only	1,58,711.70	Rupees One Lakh Fifty Eight Thousand Seven Hundred Eleven and Seventy Paise Only
8	Steel reinforcement for R.C.C. work using thermo-Mechanically Treated bars of grade Fe-500D or more including straightening, cutting, bending, placing in position and binding all complete upto plinth level as per drawings, detailed specifications and directions of the Engineer-in-charge.	kg	74,953.00	120.06	Rupees One Hundred Twenty and Six Paise Only	89,98,857.18	Rupees Eighty Nine Lakh Ninety Eight Thousand Eight Hundred Fifty Seven and Eighteen Paise Only
9	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns as per drawings, detailed specifications and directions of the Engineer-in-charge..	m ²	3,813.00	436.55	Rupees Four Hundred Thirty Six and Fifty Five Paise Only	16,64,565.15	Rupees Sixteen Lakh Sixty Four Thousand Five Hundred Sixty Five and Fifteen Paise Only
10	Supplying and laying/ fixing 110mm OD PVC pipe(class 2) buried/ above ground for drainage disposal as per drawings, detailed specifications and directions of the Engineer-in-charge.	m	92.00	338.80	Rupees Three Hundred Thirty Eight and Eighty Paise Only	31,169.60	Rupees Thirty One Thousand One Hundred Sixty Nine and Sixty Paise Only
	Total for Part B1					2,19,20,146.10	
B2	PART-B2: RECONSTRUCTION OF GV IYER ROAD WITH PAVER BLOCKS AT W/ISLAND.						

Sl. No.	Sub- heads and items of work	Unit	Approximate Quantity	Departmental Rate/ Unit Price (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
1	Scarifying metalled (water-bound) road surface including disposal of rubbish, lead upto 50 m and consolidation of the aggregate received from scarifying with power road roller of 8 to 10 tonne capacity as per detailed specifications and directions of Engineer - in-charge.	m ²	3,188.00	37.07	Rupees Thirty Seven and Seven Paise Only	1,18,179.16	Rupees One Lakh Eighteen Thousand One Hundred Seventy Nine and Sixteen Paise Only
2	Providing, laying, spreading and compacting with graded stone aggregate (size range 53 mm to 0.075 mm) (wet mix macadam (WMM)) including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paver finisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, complete as per specifications and directions of Engineer-in-Charge.	m ³	464.00	3,244.23	Rupees Three Thousand Two Hundred Forty Four and Twenty Three Paise Only	15,05,322.72	Rupees Fifteen Lakh Five Thousand Three Hundred Twenty Two and Seventy Two Paise Only
3	Providing and laying factory made 100mm thick Cement Concrete paver blocks of M-40 grade made by table vibratory method, to attain superior smooth finish using PU or equivalent moulds, laid in required colour & pattern over 50mm thick compacted bed of 6mm coarse aggregate, compacting and proper embedding / laying of inter locking paver blocks into the 6mm coarse aggregate bedding layer through vibratory compaction by using plate vibrator, filling the joints with crusher sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in drive ways or light traffic parking etc. all complete as per drawings, manufacturer's specifications & direction of the Engineer-in-Charge.	m ²	3,188.00	1,280.00	Rupees One Thousand Two Hundred Eighty Only	40,80,640.00	Rupees Forty Lakh Eighty Thousand Six Hundred Forty Only
4	Providing and laying in position cement concrete of grade 1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources, excluding the cost of centering and shuttering as per detailed specifications and directions of the Engineer - in- charge.	m ³	18.00	9,285.12	Rupees Nine Thousand Two Hundred Eighty Five and Twelve Paise Only	1,67,132.16	Rupees One Lakh Sixty Seven Thousand One Hundred Thirty Two and Sixteen Paise Only
5	Manufacturing, supplying and fixing retro reflective sign boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing , specification and direction of Engineer-in-charge. Mandatory/ Regulatory sign boards of 900 mm diameter with support length of 3750 mm.	Each	8.00	7,996.58	Rupees Seven Thousand Nine Hundred Ninety Six and Fifty Eight Paise Only	63,972.64	Rupees Sixty Three Thousand Nine Hundred Seventy Two and Sixty Four Paise Only

Sl. No.	Sub- heads and items of work	Unit	Approximate Quantity	Departmental Rate/ Unit Price (Rs)	Departmental Rate in Words	Departmental Amount in Rs.	Departmental Amount in Words
6	Manufacturing, supplying and fixing retro reflective sign boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing , specification and direction of Engineer-in-charge. Cautionary /warning sign boards of equilateral triangular shape having each side of 900 mm with support length of 3650 mm.	Each	8.00	6,189.17	Rupees Six Thousand One Hundred Eighty Nine and Seventeen Paise Only	49,513.36	Rupees Forty Nine Thousand Five Hundred Thirteen and Thirty Six Paise Only
	Total for Part B2					59,84,760.04	
	GRAND TOTAL (A1+A2+B1+B2)					8,44,82,735.30	Rupees Eight Crore Forty Four Lakh Eighty Two Thousand Seven Hundred Thirty Five and Thirty Paise Only
	BIDDER'S QUOTING AREA						
Sl. No.	Description of Work	Departmental Estimated Cost (Rs)	Percentage Quoted above/ below the		Above/ Below		
			* In Figures	*In Words			
	Percenatge Quoted above / below the Departmental Amount shown in the above Schedule	8,44,82,735.30					

* Note

- 1 Only three cells highlighted are only editable
- 2 The Bidder shall quote both in figures and words
- 3 The Bidders shall also quote Above / Below in words themselves under column (5)
- 4 Only two decimal digits will be accepted under "In Figures"
- 5 The rate filled at other places of the document are not acceptable
- 6 No condition shall be accepted